Estimated Cost: Rs. 1,07,000/-

Details of misc. work to be done							
Sl.No.	Areas		Description of work	Units	Approx. Areas	Rate	Amount
1	Ramp to the Ground near TWI room No.1	TWI gate	The existing ramp was very sharp due to Manhole, the modification needs to be done, existing ramp to be converted to staircase and staircase converted to Ramp approx. 10'X3'3". The work includes Excavation/dismantling, Brick work, Cement plaster, PCC and tile fixing (with material)	Job work	1		
2	Wall both side Ramp	TWI gate	The existing cement plaster was damaged, so after takingout the old plaster new cement plaster is to be done 1:4 ratio (with material)	Sqft	500		
3	TWI rooms no.3		Under ceiling plaster cement sand ratio 1:3	Sqft	1500		
4	TWI rooms no.3		Taking out all the wall tiles and replaster with cement. Remarks: The existing room was convert from toilts	Sqft	350		
5	TWI Room No. 1&2		Birla putty filling on wall and pillar , beam etc as per site requirements	Sqft	2000		
6	TWI paint work		OBD paint work in the TWI rooms Two and more coats as per site requirements	Sqft	10000		
7	Drinking areas		Tile Repair works includes Cement Plaster, Golas for fixing of steel Jali frame etc. as per site requirement.	Job work	5 Nos		