

Estimated Cost Rs. 1,85,000/-

Details of work to be done at swimming Pools (Tile Repair)					
Sl.No.	Description of work	Units	Areas	Approx. Rate	Estimated Cost
1	Dismantling tile work in floors and walls laid in cement mortar including stacking material within 50 meters lead. For thickness of tiles 10mm to 25mm (Dismantling of Glass mosaaic tiles from swimming pool wall and floors)	sqft	2000		
2	Providing and laying rectified glazed ceramic rectified tiles (at Swimming pool wall and Floor) of size 300X300mm or more, make Nitco, Cera, kajeria and Somani tiles, of 1st quality Oscar Blue or equivalent colour as per existing, laid on 20mm thick cement Mortar 1:3 (1cement : 3 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqmtr including pointing the joints with matching pigment etc., complete.	sqft	2000		
	Disposal of material		2000		
3	Civil work for Ramp 5'6" X 2' X 2 Nos with Tile top	Job work			
				Total	