

Estimated cost Rs. 1,75,000/-

GRINDING OF KOTASTONE AND MOSSAIC CEMENT FLOOR (RING TOILETS AND EATING AREAS)					
Sl.No.	Description of work	Unit	Qty	Rate	Amount
1	Grinding of Kota stone flooring old surface jointed with neat cement slurry, mixed with pigment to match the shade of stone including grinding.	sqft	20000		
2	Grinding of Mossaic flooring old surface jointed with neat cement slurry, mixed with pigment to match the shade of stone including grinding.	sqft	15000		

Total

Annexure "B"

Estimated Cost Rs. 1,99,000/-

Paint work in the TWI Rooms, eating areas, Toilets and North Pavilion						
Sl.No.	Description of Work	Areas	Unit	Qty	Approx. Rate in Rs.	Amount in Rs.
1	Supply and applying Distempering with Acrylic washable oil bound distemper (of approved manufacturer) two coats on old distempered work. Make : Asian, Nerolac, Berger	TWI Room	Sqft	10000		
2	Supply and applying Finishing walls with exterior decorative cement based such as snowcem, bobbiacem etc. on old work one coat to give an even shade. Make Birla sum, Birla tuff, Bombay sum,	Toilets	Sqft	5000		
3	Supply and applying Finishing walls with exterior decorative cement based such as snowcem, bobbiacem etc. on old work one coat to give an even shade. Make Birla sum, Birla tuff, Bombay sum,	Corridor wall & Pillars and eating Areas	Sqft	20000		
4	Supply and applying Painting two coats with synthetic enamel paints in all shades on old metallic or plaster or concrete surface to give an even shade including rubbing down old paint. With special quality paint. The said work is to be done up to a height of 70' and with crane.	North pavilion practice areas side facia and wall	Sqft	4000		
5	Supply and applying Distempering with Acrylic washable oil bound distemper (of approved manufacturer) two coats on old distempered work. Make : Asian, Nerolac, Berger	North pavilion inside walls, pillars etc.	Sqft	5000		